

NOTES:	REMARKS
REFERENCE	ALL DIMENSIONS TO BE CHECKED AND CORRELATED WITH ALL RELATED DRAWINGS AND ANY AMBIGUITY SHALL BE IMMEDIATELY BROUGHT TO THE NOTICE OF THE ENGINEERS BEFORE COMMENCEMENT OF THE WORK.
DIMENSION	ALL DIMENSIONS ARE MM AND LEVELS ARE IN METER. ALL DIMENSIONS ARE TO BE READ AND NOT TO BE MEASURED.
FOUNDATION/PILES	PILE WORK TO BE DONE AS PER IS 2911-2010 FILLING ON BOTH SIDES OF WALL WHEN REQUIRED SHALL BE BALANCED IN STAGES AND LAYERS.
MASONRY SPEC.	ALL MASONRY WALLS SHALL BE CONSTRUCTED FROM BURNT CLAY BRICKS UP TO SILI LEVEL WITH MIN. CRUSHING STRENGTH OF 7.5 N/mm <sup>2</sup> ON GROSS AREA UNLESS OTHERWISE SPECIFIED. BRICK MASONRY SHALL BE BEDDED WITH CEMENT : SAND MORTAR IN PROPORTION OF 1:4 UNLESS OTHERWISE SPECIFIED.
CSE BLOCK MASONRY SPEC.	ALL CSEB MASONRY WALLS SHALL BE CONSTRUCTED FROM COMPRESSED STABILIZED EARTH BLOCK WITH MIN. CRUSHING STRENGTH OF 7.5 N/mm <sup>2</sup> ON GROSS AREA UNLESS OTHERWISE SPECIFIED. CSEB MASONRY SHALL BE BEDDED WITH CEMENT : SAND MORTAR IN PROPORTION OF 1:4 UNLESS OTHERWISE SPECIFIED.
CONC. SPEC.	ALL CONCRETE MIX M25 UNLESS OTHERWISE SPECIFIED.
REINFORCEMENT	INDICATES TMT STEEL (Fe 500D) OF YIELD STRENGTH 500 N/mm <sup>2</sup>
COVER	CLEAR COVER TO MAIN STEEL IS AS FOLLOWS PILES : -50 mm PILE CAP : -60 mm GRADE BEAM : -30 mm FOOTINGS : -50 mm SIDES & TOP : -50 mm BOTTOM : -50 mm COLUMNS & PEDESTALS : -40 mm BEAMS & LINTELS : -30 mm SLABS : -25 mm LAP LENGTH IS FIFTY TIMES BAR DIAMETER
LAPS/SPLICES	
SPECIAL NOTE :	THE BUILDING IS DESIGNED FOR G+3 STOREYS ONLY AND NO FUTURE PROVISION IS CONSIDERED.
LEGENDS:	 COLUMN/WALL STARTS FROM THIS LEVEL COLUMN/WALL STOPS AT THIS LEVEL

FOR TENDER PURPOSE ONLY

No.	Date.	Remarks.

Date	Prints	Issued to	Date	Prints	Issued to

Distribution of Prints

- Consultants**
- **Structural Consultants**  
VINOD SHAH Consulting Engineers Pvt. Ltd.
  - **Services Consultants**  
DBHMS
  - **Landscape Consultants**  
Earthscape Consultancy Pvt Ltd
  - **Road and Pathways Consultants**  
Arhmm Infra Consultants LLP


Project  
**Nalanda University, Rajgir, Bihar**

Title  
**STRUCTURAL G.A. DRAWINGS OF TERRACE PLAN AND DETAILS FOR FACULTY HOUSING (APPT. TYPE-3)**






Dealt : HS  
Checked : AJ  
Scale : 1:50, 1:25  
Date : 07/09/2016

Drawing No.  
NUC-FAH(3)-S-A.8

**VASTU SHILPA CONSULTANTS**  
Architects | Planners | Urban Designers



TERRACE PLAN AT +13.150M LVL(UNF.F.L.)  
(ALL SLABS 135 THK. UNLESS SPECIFIED OTHERWISE)  
(BEAM B10 OMITTED)



SECTION F-F